


LAYOUT



A- FRONTAL VIEW


Drawer unit with telescopic guide stainless steel with shock absorber

Steel dustbin with telescopic guide stainless steel with shock absorber


ITEM	QTY	SOURCE	DESCRIPTION	L MM	D	H
PREPARATION						
27	1	FABRICATOR	Stainless steel worktop with basin, underneath cupboard compartment, drawer unit and free compartment for inserting refrigerated table	2110	800	900
27.1	1	FABRICATOR	Prep Sink			
28	1	FABRICATOR	Double Wall Shelf, Bracketless	2100	420	50
29	1	ELECTROLUX PROFESSIONAL	Refrigerated work top gn 1/1 temperature -2°/+8°c without top	900	690	810
30	1	ELECTROLUX PROFESSIONAL	hand sink w/ soap & towel disp. floor standing with waste compartment and knee control, 1 bowl	400	400	900
COLD STORAGE						
31.1	1	ELECTROLUX PROFESSIONAL	670l 1 door fridge -2°/+10°c, digital, with light (i290)	710	835	2050
31.2	1	ELECTROLUX PROFESSIONAL	1430 lt 2 door fridge -2°/+10°c, digital, with light (i290)	1441	835	2050
32	1	ELECTROLUX PROFESSIONAL	1430 lt 2 door fridge -2°/+10°c, digital, with light (i290)	1441	835	2050

NOTE GENERALI:

- tutte le misure sono da verificare sul luogo;
- la posizione della baionetta è da verificarsi in sede di costruttivo;
- le altezze si considerano dal pavimento finito al controsoffitto;
- le dotazioni impiantistiche sono riportate nelle specifiche tavole "20011 PE F&B 03-04";
- la legenda completa è riportata sulla tavola "20011 PE F&B 06";
- i dettagli esecutivi di massima sono riportati nella tavola dedicata;



B- SIDE VIEW



COMUNE DI MILANO  
CONSTRUCTION DOCUMENTATION

Property  
AST VENEZIA S.R.L.

Via Borgonuovo, 9  
20121 Milano

Tenant  
RH MILAN S.R.L.

Vicolo San Giovanni sul muro, 9  
20121 Milano



CONSULTANT'S TEAM

**BMS Progetti s.r.l.**  
piazza santissima trinità 6  
20154 milano  
bmsprogetti.it

Designer  
ing. Aldo Bottini  
Consultants  
SMP studio  
PAN studio  
Jensen Hughes

Ristrutturazione Edilizia - Corso Venezia 56

TITLE				SCALE		
Dettaglio preparazioni e stoccaggio freddo piano B02				1:20		
DOCUMENT				ISSUE		
20011 PE F&B 110				05/02/2025		
REV	DATE	DESCRIPTION	EDITED	VERIFY	APPROVED	
00	05/02/2025	90% CD Submission	MR	CC	AM	
01	07/03/2025	Tender Package	MR	CC	AM	

PE  
F&B  
110